BRUHAT BANGALORE MAHANAGARA PALIKE
YELHANKA ZONE ELECTRICAL DIVISION

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of Work:- Providing and laying Aerial Bunched Cables/poles/panel boards to Palanahalli road in ward no 5

Sl.No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	1500	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 25 + 1 X 25 SQ.MM KPWD ELE SR 2014-15	Per Mtr	140.00	Rupees One Hundred Forty Only
2	1500	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM SR	Per Mtr	10.00	Rupees Ten Only
3	2000	Supplying and stringing of ACSR Conductor (6/2.59mm Al +1/2.59mm Steel).34/5.11 KPWD ELE SR 2014-15	MTR	30.00	Rupees Thirty Only
4	70	1.1 KV Pin Insulator 34/5.9.1 KPWD ELE SR 2014-15	Nos	40.00	Rupees Forty Only
5	20	No. 8 Strain Insulator 33/5.4.3 KPWD ELE SR 2014-15	Nos	12.00	Rupees Twelve Only
6	52	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps 25kA.26/5.14.1	Each	4500.00	Rupees Four Thousand Five Hundred Only
7	52	Supply and Installation / Fixing / Provision of Pole box with HRC Fuse / MCB provision and suitable connector / terminal for 3 Ph / 1 Ph connections with Loop-In & Loop-Out terminals for 10 Sqmm / 25 Sqmm 3.5 C Al/Ar / Cu/Ar Cable and branch out 2.5 Sqmm 2 core Al/Cu PVC Insulated cable, enclosed in a Thermoplastic, Polystyrene enclosure, which should be shock proof, safe, IP65(Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP65 Thermoplastic, polyamide glands and/or grommets.200mmx200mmx98mm	Each	1900.00	Rupees One Thousand Nine Hundred Only
8	100	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.4 core 16 sqmm40/6.4.4	Mtrs	140.00	Rupees One Hundred Forty Only
9	93	Labour charges for laying of 1.1 KV class UG cable when supplied agency in existing trench Gl pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct. 6 sqmm to 16 sqmm41/6.5.1	Mtrs	30.00	Rupees Thirty Only
10	60	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete.41/6.6.1	Mtrs	76.00	Rupees Seventy Six Only
11	40	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or consealed system of wiring.I Group A Materials.6 sqmm 6/2.3.3	Mtrs	60.00	Rupees Sixty Only

12	2	Thiristor based single/ Three phase smart street light control and monitoring system Remotely control and and monitorable smart street light system by using web or mobile application .smart control system has hardware ruggedness over field issues like line cross, line short, lighting and any other irregularities in voltage. It has some features like 1.Remote lighting management.2.Precise lighting turnoff.3.Load ballancing.4.Load power regulation.5.Status tracking. It works on the basis of some of these features 1) Main Control Unit (Mother board) : Handles controlling , data handling and other communication process. 2) Communication unit: GSM/GPRS quad bandwith RS232 interface wireless communication unit 3) Gate Driver Unit: Firing angle controllable board for driving the thyristor 4) Switching Thyristor: SCR 110 AMPS dual thyristor modules for switching 5)Embedded Firmware: Firmware to control , handle , process the data and communicate it wirelessly.6) Metal Enclosure : IP66 weather prof metal enclosure. 7) transformers: Customized step down transformers for various purposes.8) Wiring and other device assembly components.	No	50000.00	Rupees Fifty Thousand Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

Contractor

For POWER MAC

Proprietor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone